

Redevelopment Plan

Trollinger- Stonebridge

Block 302, Lots 14, 26, 27, & 49


Medford Township, Burlington County, New Jersey



**INTRODUCTION
COPY**



Prepared By: Taylor Design Group, Inc.



Scott D. Taylor, PP, AICP, LLA, LEED-AP
*The original of this document has been signed
and sealed in accordance with New Jersey Law.*

Report Date: **February 27, 2026**

Introduced: **March 3, 2026**

Adopted: _____

Medford Township Council Members

Michael Czyzyk, Mayor
Michelle Voorhees, Deputy Mayor
Bethany Milk
Raymond W. Coxe
Katherine Santamore



Medford Township Planning Board Members

Michael Czyzyk, Mayor (Class I)
Marty Hamilton (Class II)
Bethany Milk, Councilwoman (Class III)
Thomas Juliano, Chairman (Class IV)
Clark Perks, Vice Chairman (Class IV)
Chad Muckenfuss (Class IV)
Donna Symons (Class IV)
Sarah Cooper (Class IV)
Darrin Gould (Class IV)
Vittorio Anepete (Alternate 1)
Andrew Lavecchia (Alternate 2)

Township Staff & Board Professionals

Daniel Hornickel, Township Manager
Ann Bell, AICP, PP, Director of Planning & Enforcement, Zoning Officer
Gregory McGuckin, Esq., Township Attorney
Anthony T. Drollas, Esq., Board Attorney
Christopher J. Noll, PE, PP, CME, Board Engineer
Scott D. Taylor, AICP, PP, LLA, LEED-AP, Board Planner
Henry S. Snyder, Planner

I. Introduction

The Supreme Court of New Jersey has held that all municipalities within the State must fulfill their constitutional obligation by planning for and facilitating their fair share of the region’s affordable housing needs. These obligations are quantified and assigned to each municipality and must be addressed through a Housing Element and Fair Share Plan, which outlines how the municipality intends to address their constitutional obligation. As reaffirmed by the Court, municipalities must also provide the zoning mechanisms that will enable realistic opportunities for the development of affordable housing.

The Medford Township Planning Board adopted a **2025 Housing Element and Fair Share Plan** on June 17, 2025, and adopted an *amended* Housing Element and Fair Share Plan on December 18, 2025, prepared by Environmental Resolutions Inc., which Plan identified parcels as sites for inclusionary development which will include both market rate units and affordable housing units.

Implementation of the adopted Housing Element and Fair Share Plan will require the rezoning of the individual parcels identified in the plan, to provide for the Township’s constitutional affordable housing obligation.

While traditional rezoning could be utilized to achieve the required changes to the permitted unit types and density, Township Council has determined that the more effective planning mechanism is to create a **Redevelopment Plan** that includes modified zoning and specific design standards for the inclusionary/affordable development sites under the Local Redevelopment and Housing Law, N.J.S.A. 40A:12A-1, et seq. (“LRHL”). This process affords greater control over the quality and character of the required inclusionary development, particularly with respect to architectural design, buffers, lighting, open space and related site improvements.

Redevelopment Plan Preparation Process

On January 17, 2017 the Medford Township Council authorized by Resolution 32-2017, and Amended March 7, 2017, the Medford Township Planning Board to undertake an investigation to determine whether certain identified parcels meet the statutory criteria to be considered an **Area in Need of Redevelopment, Without Condemnation**, pursuant to the Local Redevelopment and Housing Law (LRHL) (N.J.S.A. 40A:12A et seq.)

Block 302, Lots 14, 26, 27, & 49.

The Preliminary Investigation Report dated March 29, 2017, was prepared by Taylor Design Group, Inc., Scott D. Taylor, PP, AICP, LLA, LEED-AP, Consulting Planner.

The Planning Board conducted a public hearing on January 28, 2026, and determined that multiple statutory criteria of N.J.S.A. 40A:12A-5 were met, and that the above mentioned parcels may be designated as an **Area in Need of Redevelopment, Without Condemnation**. (See Aerial Location Map and Tax Map figures below,)


On **February 3, 2026**, by Resolution 45-2026, the Medford Township Council designated the Park View at Kirby’s Mill Area, Block 803, Lots 6.01 & 6.02, as an Area in Need of Redevelopment, Without Condemnation.

Designation as a Non-Condemnation Redevelopment Area **does not entitle the municipal government to acquire property via eminent domain.**


Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

This Redevelopment Plan has been prepared to meet specific court mandated timelines for adoption of the Ordinances necessary to implement the previously adopted **2025 Housing Element and Fair Share Plan**, and will provide a mechanism for the orderly planning and development of the designated Redevelopment Area. This Plan has been prepared pursuant to the LRHL, N.J.S.A. 40A:12A-7 which provides, “no redevelopment project shall be undertaken or carried out except in accordance with a Redevelopment Plan adopted by ordinance of the municipal governing body, upon its finding that the specifically delineated Redevelopment Area is located in an Area in Need of Redevelopment or in an area in need of rehabilitation, or in both...”

Tax Map- Courtesy of Medford Township.



Aerial Location Map- Aerial Imagery courtesy of Google Earth Pro © 2025.



II. Statutory Requirements

This Redevelopment Plan will become the formal planning document for the redevelopment of the above identified parcels in the designated *Redevelopment Area*. In accordance with the requirements of the LRHL, this Redevelopment Plan includes an outline for the planning, development, redevelopment, or rehabilitation area sufficient to indicate:

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

1. Its relationship to definite local objectives as to appropriate land uses, density of population, and improved traffic and public transportation, public utilities, recreational and community facilities and other public improvements;
2. Proposed land uses and building requirements in the project area;
3. Adequate provision for the temporary and permanent relocation, as necessary, of residents in the project area, including an estimate of the extent to which decent, safe and sanitary dwelling units affordable to displaced residents will be available to them in the existing local housing market;
4. An identification of any property within the redevelopment area which is proposed to be acquired in accordance with the redevelopment plan;
5. Any significant relationship of the redevelopment plan to (a) the master plans of contiguous municipalities, (b) the master plan of the county in which the municipality is located, and (c) the State Development and Redevelopment Plan adopted pursuant to the “State Planning Act,” P.L. 1985, c.398 (C52:18A-196 et. al.);
6. A housing inventory of all affordable housing units to be removed;
7. A plan for replacement of any affordable housing removed pursuant to the Redevelopment Plan;
8. Proposed locations for public electric vehicle charging infrastructure within the project area in a manner that appropriately connects with an essential public charging network.

III. Description of the Redevelopment Area

General Description and Surrounding Area

The designated *Redevelopment Area* is comprised of 4 lots totaling approximately 164.38 acres located north east of the Medford-Mt. Holly Road (CR 541) and Church Road intersection, as shown on the Aerial Location Map and Tax Map figures above.

The property is in the Agriculture Retention AR Zone and has been primarily used for agriculture since at least 1931. The tract also contains large areas of wooded lands. The site contains approximately 1,000 linear feet of frontage along County Route 541, with limited frontage along Church Road at Lot 49 and at the abandoned railroad right-of-way.

Block 302, Lot 14 is a 91.99 acre parcel located within the AR Agriculture Retention Zoning District. This lot has approximately 1,000 linear feet of frontage along County Route 541. The lot is classified as 3A (Farm Property).

Lots 26, 27, and 49 are a total of 72.39 acres. These parcels are also located within the AR Agriculture Retention Zoning District. Lots 27 and 49 have minimal frontage on Church Road, while the remaining parcels do not front on any roads.

The commercial uses on the east side of CR 541 from north to south include a vacant standalone converted residential structure, a shopping center containing various restaurants, retail and service commercial uses, standalone animal clinic (Animal Eye Clinic), and the Eagle Autobody with Enterprise Rental Agency. The Dr. Still Historic site and scattered residential uses front on Church Road, south of the property. Across Church Road are residential

developments and scattered residential uses, as well as a proposed Dunkin’ Donuts at the southeast corner, which is under construction. West of County Route 541 is a commercial auto supply shop. The Fellowship Alliance Chapel (FAC) owns most the remaining properties which include a place of worship and associated accessory uses in standalone scattered buildings located in the PPE/CS Parks Public Education zone with Community Service Overlay. A small shopping center containing restaurant, WaWa convenience store, and service and retail commercial uses is located at the southwest quadrant of the intersection.

Scattered residential uses located in the Agricultural Retention AR Zone, fronting on CR 541 are located north and west of the subject site.

Township Context

Medford Township is located in Burlington County, and is bordered by multiple municipalities. To the north are Mount Laurel and Lumberton Townships. Southampton and Tabernacle Townships are located to the east. To the south are Shamong and Waterford Townships, and Evesham Township is located to the west. Medford Lakes Borough is located in the eastern portion of the Township, and is surrounded by Medford.

Medford Township is located at the edge of the Philadelphia Metropolitan Region to the west, and the New Jersey Pinelands National Reserve to the southeast. The northern portion of the community is considered an inner lowland of the Delaware River where forests and agriculture are the prevailing land uses. The majority of the Township is within the Atlantic Outer Coastal Plain, characterized by oak and pine forest, wooded wetlands, surface lakes and streams, and cedar bogs. The southern portion of the Township is located within the jurisdiction of the Pinelands, with Route 70 being the northern boundary.

IV. Redevelopment Plan Vision, Goals & Objectives

Redevelopment Area Vision

The overall vision of this Redevelopment Plan is to create a new residential community that includes both market rate units and affordable housing units for the Township to fulfill its constitutional obligation to provide their fair share of the region’s affordable housing needs, as set forth in the adopted Housing Element and Fair Share Plan.

This Redevelopment Plan will provide a framework to create a neighborhood that will complement the existing surrounding uses and neighborhoods, and the overall character of Medford Township, with a particular focus on architectural design, buffers, low impact lighting, open space, pedestrian connectivity and related site improvements.

Township Master Plan & Past Redevelopment Plans

Every Medford Township Master Plan document notes the importance of ensuring consideration is given to the Supreme Court of New Jersey ruling which held that all municipalities within the State must fulfill their constitutional obligation by planning for and facilitating their fair share of the region’s affordable housing needs.

It is the overall goal of the **2025 Housing Element and Fair Share Plan**, in the Land Use Plan, to provide the planning context in which access to low and moderate-income housing can be

provided by the requirements of the Fair Housing Act and the laws of the State of New Jersey while respecting the character and density of the Township of Medford.

The **2024 Master Plan & Development Regulations Reexamination Report**, dated June 6, 2024, highlights these efforts as discussed below.

Task 3.0 Redevelopment Plans: *The recommendations of the planning board concerning the incorporation of redevelopment plans adopted pursuant to the “Local Redevelopment and Housing Law,” P.L. 1992, c.79 (C.40A:12A-1 et al.) into the land use plan element of the municipal master plan, and recommended changes, if any, in the local development regulations necessary to effectuate the redevelopment plans of the municipality.*

Redevelopment Area Goals & Objectives

A. Plan Goals

The goals of the Redevelopment Plan are consistent with the following goals outlined by the Medford Township Master Plan, and as characterized in the 2014 and 2017 Reexamination Reports.

- 1) Promote the establishment of appropriate population densities in concentrations that will contribute to the well-being of persons, neighborhoods, and the region, and the preservation of the environment.
- 2) Provide sufficient space in appropriate locations for a variety of residential and commercial uses to meet the needs of citizens.
- 3) Promote the conservation of open space and natural resources to prevent sprawl and degradation of the environment through improper use of the land.
- 4) Promote a desirable visual environment through conservation and preservation of valuable natural features.
- 5) Preserve the rural character of the Township through zoning.

B. Plan Objectives

- 1) Provide an attractive residential housing opportunities to meet the needs of a variety of household types.
- 2) Through good civic design and development techniques, create high quality spaces to facilitate social interaction and foster community involvement while preserving areas of steep slopes and environmentally sensitive lands, and providing appropriate buffers.

V. Land Use Plan

Relationship to Township Land Development Regulations

The standards contained within this Redevelopment Plan shall supersede the development regulations of the existing Township Code where specifically indicated, particularly in the instance of required and permitted uses, residential density, bulk standards, buffers and general design standards for the Redevelopment Area.

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

Where regulations of this Plan conflict with the Township’s development regulations, this Plan shall control; where this Redevelopment Plan is silent, the Township’s development regulations shall apply.

The Redevelopment Plan adopts and incorporates by reference Chapter DR: Development Regulations of the Township of Medford, and all other applicable land use and related regulations of the Township of Medford that are not expressly modified herein.

Site Plan and/or Subdivision Application and Approval

The Medford Township Planning Board, pursuant to the provisions of the L.R.H.L. N.J.S.A. 40A:12A-13 and the Municipal Land Use Law, N.J.S.A. 40:55D-1 et. seq., shall conduct site plan and/or subdivision review as applicable, for any proposed development in the Area, upon submission of a complete application for development, consistent with the NJ Municipal Land Use Law and Local Ordinances.

Exceptions from Standards

Bulk or “c” variances per N.J.S.A. 40:55D-70(c) from the development requirements, and design waivers per N.J.S.A. 40:55D-51 from the standards set forth by this Redevelopment Plan may be necessary in certain limited circumstances. In such instances, the Planning Board may grant variances and waivers, where it is demonstrated that such relief will not substantially impair the intent of the Redevelopment Plan and will not present a substantial detriment to the public health, safety and welfare, consistent with the Municipal Land Use Law.

Any use or “d” variances per N.J.S.A. 40:55D-70(d), including, but not limited to deviations from the permitted uses, conditional uses, maximum floor area ratio, permitted density, or height (by 10 feet or 10% of the maximum height) within the Redevelopment Area shall be permitted only by means of an amendment of the Redevelopment Plan by Township Council, should the deviation be considered acceptable to the furtherance of the goals and objectives of this plan.

Provisions Related to Off-Site Improvements

The extent of the Redeveloper’s responsibility for any installation or upgrade of infrastructure related to its project, whether on-site or off-site, shall be as outlined in a Redevelopment Agreement. All infrastructure improvements shall comply with applicable local, state, and federal codes including the Americans with Disabilities Act.

This Redevelopment Plan envisions a sidewalk to be provided along the Route 541 right of way connecting from the Redevelopment Area to the Church Road Intersection. The terms of this sidewalk construction, along with any potential need for right of way and/or easements will be as fully set forth in a Redevelopment Agreement.

Creation of the Trollinger Stonebridge Redevelopment Area Zoning District

This Redevelopment Plan hereby creates and establishes the *Trollinger Stonebridge Redevelopment Area (TSRA)* Zoning District, which shall govern the development of the identified parcels included in this Redevelopment Plan, known as Block 302; Lots 14, 26, 27, & 49.


Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

The approximate boundaries of the various development components are as generally set forth in the Development Component Map below, and are as follows:

- Senior Twin Component
- Inclusionary Townhouse Component
- Single Family Component

In addition, the project includes the construction of a 10' wide Regional Bike Trail along the eastern portion of the site within the former Railroad Right-of-Way lot.

Component Map



As described above, as permitted by Statute, this Redevelopment Plan may be amended in the future by the Redevelopment Entity to address specific proposals for any properties located within the designated Redevelopment Area.

VI. District Standards

Concept Plan Vision and Approach

This Redevelopment Plan and the standards for the *Trollinger Stonebridge Redevelopment Area (TSRA) Zoning District* set forth herein establish a comprehensive framework for the redevelopment of the parcels within the Zone. This will require subdivisions and site plan approval for all parcels within the **Redevelopment Area** to effectuate the referenced redevelopment. This comprehensive approach will:

- Create a new residential community that includes both family and age restricted market rate units and affordable units for the Township to fulfill its constitutional obligation to provide their fair share of the region’s affordable housing needs, while striving to fit within the character of the existing community.
- Include enhanced perimeter buffers around the property of 50’.
- Provide for construction of a Regional Trail connection.

All Redevelopment proposals and Site Plan applications shall comply with the standards set forth in *Chapter DR- Development Regulations*, except as expressly modified herein; and shall generally consist of the following, as shown on the Concept Plan below.

- **Senior Twin Component**
 - **36 Age-Restricted, Affordable Twin Units**
- **Inclusionary Townhouse Component**
 - **12 Affordable Stacked Townhouse Units**
 - **Up to 113 Market Rate Townhouse Units**
- **Single Family Component**
 - **Up to 139 Market Rate Single Family Homes**
- New roadways, sidewalks, parking, amenities, perimeter buffers and related improvements, as more fully described below.
- A portion of the northeastern undeveloped section of the site will be dedicated to Medford Township for use as a potential future Affordable Housing location, if needed. The final configuration, and area to be dedicated, and the area to remain as HOA Open Space will be determined at the time of Site Plan Approval, as determined by the Township. The final terms will be as fully set forth in a Redevelopment Agreement.
- The project includes the construction of a 10’ wide Regional Bike Trail along the eastern portion of the site within the former Railroad Right-of-Way. The constructed Trail and the area of Lot 27 will be dedicated to the Township, or to Burlington County, at the discretion of Medford Township.
- This Redevelopment Plan envisions a sidewalk to be provided along the Route 541 right-of-way connecting from the Redevelopment Area to the Church Road Intersection, to be constructed by the Redeveloper, subject to the existence of adequate right-of-way to construct the sidewalk in front of existing properties. In the absence of adequate right-of-way, the Township will be responsible to obtain any necessary sidewalk easement to facilitate the construction. The terms of this sidewalk construction, along with the responsibilities for right of way and/or easement acquisition, or payments in lieu construction, will be as fully set forth in a Redevelopment Agreement.

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ


The Site Plan Drawings and Architectural Plans and Elevations to be submitted to the Planning Board for Subdivision and Site Plan Approval shall be substantially consistent with the Conceptual Plans, Elevations and Renderings included in this Plan, to effectuate the redevelopment. The standards enumerated herein are intended to supplement and clarify the intent of the Concept Plans.

All Plans shall be submitted to the Redevelopment Entity/Township Council for review and approval **prior** to any submission of an Application to the Planning Board. This shall include a detailed phasing plan for the project, and any subcomponents, including the production of affordable units.

Prior to any submission of an Application to the Planning Board, the Redeveloper shall submit a Fiscal Impact Analysis that examines the future municipal service costs that could be expected to result from the redevelopment as outlined in this Redevelopment Plan.

This analysis should provide a comparison of revenues to costs associated with new development, and impacts to municipal services, infrastructure and the like.

Overall Rendered Concept Plan- Full Size Layout Plan inserted as Appendix A.



Trollinger Stonebridge Redevelopment Area (TSRA) Zoning District

Within the **Trollinger Stonebridge Redevelopment Area (TSRA) Zoning District**, the following standards shall apply:

A. Definitions

For the purposes of this Redevelopment Plan, the following definitions shall apply in addition to those in the Medford Ordinances. Where a conflict exists, the definitions of the Redevelopment Plan shall control.

Age Restricted/Senior/Active Adult (Used Interchangeably): A housing unit designed to meet the needs of, and exclusively for, the residents of an age-restricted segment of the population where the head of the household is a minimum age of either 62 years, or 55 years and meets the provisions of 42 U.S.C. §§ 3601 et seq, except that due to death, a remaining spouse of less than 55 years of age shall be permitted to continue to reside in the unit. The household may not have any school aged children under the age of 18.

Common Open Space: Land and/or water within or related to a development or neighborhood, designed and intended for the use or enjoyment of all residents of the development or neighborhood and shall include complementary improvements that benefit the residents and property owners within the development or neighborhood. Common Open Space shall be owned and maintained by a Homeowners Association, or may be owned by the municipality, at the discretion of the Township. Common Open Space may include environmentally constrained areas such as flood hazard areas, wetlands, wetland buffers, non-wetland buffers, stormwater management areas and recreation areas.

Density, Gross: The total number of dwelling units divided by the total area of the tract (in acres).

Lot, Corner: A lot on the junction of land abutting two or more intersecting streets where the interior angle of intersection does not exceed 120°. For the purposes of this Redevelopment Plan, a corner lot shall have one front yard, two side yards and one rear yard. The front yard is considered where the garage or driveway is located. The rear yard is opposite the front yard, and the remaining yards are side yards.

Overall Tract: The total area of land within the redevelopment area that is the subject of a coordinated redevelopment plan and application, and may include multiple lots, the removal or consolidation of lot lines, and the subdivision of lots. The overall tract includes wetlands, wetland buffers, flood hazard areas, floodways and riparian zones.

Stacked Affordable Townhouse: A dwelling that is designed and occupied exclusively as the residence of one housekeeping unit, where each dwelling has at least one full floor for occupancy between one or more common vertical walls and one horizontal floor all housed in **the same structure.**

Twin Dwelling Unit: A two-family dwelling unit building where the family dwelling units are separated by a vertical party wall unpierced except for access to the outside or to a common basement, with each unit being on its own fee simple lot.

B. Permitted Principal Uses

- An inclusionary Community of not more than 300 total units, consisting of the following:
 - Senior Twin Component
 - 36 Age-Restricted, Affordable Twin Units on fee simple lots
 - Inclusionary Townhouse Component
 - 12 Affordable Rental, 3-Bedroom Stacked Townhouse Units
 - Up to 113 Market Rate, 3 or 4 Bedroom Townhouse Units on fee simple lots
 - Single Family Component
 - Up to 139 Market Rate For Sale, Single Family Homes on fee simple lots

The unit/bedroom mix requirements, affirmative marketing requirements, candidate qualification and screening, and the integration of the affordable buildings with the market rate community shall comply with the Uniform Housing Affordability Controls, the Township’s Housing Element and Fair Share Plan, the Township’s Affordable Housing Ordinance, any applicable order of the court, all other applicable laws, and the Concept Plan included herein, and shall be the subject of a Redevelopment Agreement. Units shall include very low, low, and moderate-income housing units.

More than one Stacked Townhouse Unit is permitted on a single lot as provided for on the Concept Plan.

C. Permitted Accessory Uses

1. Indoor and outdoor recreational facilities (including but not limited to playgrounds, bike racks/storage buildings, tot lots, pavilions, grills, walking trails, outdoor furniture, etc.)
2. Trash and recycling enclosures
3. Mailbox clusters, package drop off/locker locations
4. Retaining walls
5. Model Homes and temporary parking associated with the model homes, for sales and leasing purposes
6. Signage (Permanent and Temporary)
7. Construction Trailers
8. Electrical Vehicle Charging Stations and Service Equipment
9. Generators and Air Conditioning Condenser Units
10. Decks and Patios
11. On and off street parking
12. Public water and public sewer utility infrastructure
Maintenance Building
13. Fire suppression equipment and sheds to shield and contain such equipment as necessary for all residential structures
14. Above and below ground utilities including but not limited to heated enclosures, sanitary pump station, water storage facilities, cable television and telephone boxes, electrical transformers and other utilities that are customary to a residential development which shall have no buffer or setback requirements
15. Above and below ground stormwater management areas
16. For Townhouse Lots:

- a) Fences, located in a rear yard or side yard only, not exceeding 6' in height, and subject to all other requirements of §513. Fences are not permitted in a front yard. Deer fences are not permitted.
17. For Senior Twin Lots:
- a) Fences, located in a rear yard or side yard only, not exceeding 6' in height, and subject to all other requirements of §513. Fences are not permitted in a front yard. Deer fences are not permitted.
 - b) Sheds, located in a rear yard only, not exceeding 15 feet in height to the peak, not closer than 5' to a rear or side lot line, and subject to all other requirements of Chapter DR. One shed is permitted per lot, and shall not exceed 168 square feet in area.
18. For Single Family Lots:
- a) Swimming pools, located in a rear yard only, no closer than 5' to a rear or side lot line, and subject to all other requirements of §529.
 - b) Fences, located in a rear yard or side yard only, not exceeding 6' in height, and subject to all other requirements of §513. Fences are not permitted in a front yard. Deer fences are not permitted.
 - c) Sheds, located in a rear yard only, not exceeding 15 feet in height to the peak, not closer than 5' to a rear or side lot line, and subject to all other requirements of Chapter DR. One shed is permitted per lot, and shall not exceed 168 square feet in area.

D. Bulk/Dimensional Requirements

- 1. The following bulk/dimensional standards shall apply:

Zoning Dimensional Regulations	
Standard	Requirement
Overall Tract Standards	
Overall Tract Lot Area (Min.)	100 acres
Overall Tract Lot Frontage (Min.)	500'
Overall Tract Lot Width (Min.)	500'
Overall Tract Lot Depth (Min.)	500'
Tract Perimeter Buffer to Regional Trail (Min.)	10'
Tract Perimeter Buffer all Others (Min.)	50'
Tract Perimeter Building Setback- Unit (Excludes Decks) (Min.)	70'
Tract Perimeter Setback to New Road or Parking (Min.)	50'
Residential Gross Density (Max.)	2.0 units per acre
Minimum Number of Affordable Units	48
Maximum Number of Market Rate Units	252
Maximum Number of Total Units	300
Tract Building Coverage Limit (Max.)	20%
Lot Coverage Limit (Max.)	45%
Common Open Space (Min.)	20%
Building Height	39' & 2.5 Stories
Parking- Standard Spaces (Including Accessible spaces)	Per RSIS
Parking- EV Spaces (Including Accessible EV spaces)	Per NJ Law
Accessory Structures	
Side Yard Setback (Min.)	5'
Rear Yard Setback (Min.)	5'
Setback to other Buildings (Min.)	5'
Internal Front Yard Setback (Min.)	5'
Maximum Height (Excludes Water Storage Tanks)	20'

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

Market Rate Townhouses	
Lot Area- (Min.)	2,800 SF
Maximum Number of Market Rate Units	113
Interior Unit Lot Width (Min.)	28'
End Unit Lot Width (Min.)	33'
Lot Depth (Min.)	100'
Front Yard Setback- Right-of-Way to Building Face (Min.)	20'
Side Yard Setback- Internal units	N/A
Side Yard Setback – End Units	4.5'
Side Yard Setback – End Unit Side Entry Porch	.5'
Rear Yard Setback- Unit	15'
Rear Yard Setback- Patio or Deck	10'
Side Yard Setback- Patio or Deck- Interior Unit	0'
Side Yard Setback- Patio or Deck- End Unit	5'
Driveway Setback (Min.) Subject to Engineering Approval.	0'
Lot Coverage Limit (Max.)	87.5%
Building Coverage Limit (Max.)	70%
Distance Between Buildings- (Min.)	35'
Distance Between Buildings and Decks or Patios (Min.)	25'
Maximum Building Length	240'
Maximum Units per Building	8
Minimum Number of Units per Building	3
Maximum number of Bedrooms per Unit	4

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

Affordable Stacked Townhouses	
Lot Area- (Min.)	15,000 SF
Minimum Number of Affordable Units	12
Lot Width (Min.)	150'
Lot Depth (Min.)	100'
Front Yard Setback- Property Line to Building (Min.)	20'
Front Yard Setback- Curb Line to Building (Min.)	15'
Side Yard Setback (Min.)	10'
Lot Coverage Limit (Max.)	65%
Building Coverage Limit (Max.)	45%
Distance Between Buildings- (Min.)	35'
Distance Between Buildings and Decks or Patios (Min.)	25'
Rear Yard Setback (Min.)	10'
Maximum Building Length	210'
Maximum Units per Building	12
Accessory Structures	
Side Yard Setback (Min.)	5'
Rear Yard Setback (Min.)	5'
Setback to Other Buildings (Min.)	5'
Internal Front Yard Setback (Min.)	5'
Maximum Height (Excludes Water Storage Tanks)	20'

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

Senior Twin- Affordable	
Lot Area- (Min.)	4,600 SF
Number of Units- Required and Permitted	36
Lot Frontage (Min.)	40'
Lot Width (Min.)	40'
Lot Depth (Min.)	115'
Front Yard Setback- Right-of-Way to Building Face (Min.)	20'
Side Yard Setback-	10'
Side Yard Setback- Between Units	0'
Side Yard Setback- Side Entry Porch	5'
Rear Yard Setback- Unit	25'
Rear Yard Setback- Patio or Deck	15'
Side Yard Setback- Patio or Deck- Interior	0'
Side Yard Setback- Patio or Deck- Exterior	5'
Driveway Setback (Min.) Subject to Engineering Approval.	0'
Building Coverage Limit (Max.)	40%
Lot Coverage Limit (Max.)	50%


Single Family	
Lot Area- (Min.)	7,200 SF
Maximum Number of Units	139
Lot Width (Min.)	60'
Lot Depth (Min.)	120'
Front Yard Setback- Right-of-Way to Building Face (Min.)	20'
Side Yard Setback- Unit	7.5'
Rear Yard Setback- Unit	25'
Rear Yard Setback- Patio or Deck	10'
Side Yard Setback- Patio or Deck	7.5'
Driveway Setback (Min.)	5'
Building Coverage Limit (Max.)	50%
Lot Coverage Limit (Max.)	65%

2. In the calculation of Building Height, where any finished grade at a building corner is three feet or more above the original grade, the original grade at such building corner(s) shall be utilized in the calculation of Building Height.
3. Garage trellises and eaves may extend up to 2' into required setbacks. Fireplaces may extend up to 2' into required side or rear yard setbacks.
4. Unenclosed roofed porches for side entry Townhouse End Units may extend into the required side yard setbacks up to 4', plus an additional roof overhang of up to 1', but shall not cross the property line.
5. Unenclosed roofed porches for entries may extend into the required front yard setbacks up to 4', plus an additional roof overhang of 1'.
6. The New Jersey Residential Site Improvement Standards shall apply to all residential development, including but not limited to site accesses, road widths, sidewalks and parking requirements.
7. Fences as set forth herein, or in accordance with DR §513, where this plan is silent.
8. Temporary construction trailer(s) in accordance with Chapter DR are permitted, provided they are:
 - a. Setback at least 20' from all property lines,
 - b. Shown on the approved site plan,
 - c. Removed within 30 days of occupancy of the last building on the site, or after a period of 90 consecutive days where construction has ceased on the site.
9. Temporary sales/rental office trailer(s) are permitted, provided they are:
 - a. Setback at least 20' from all property lines,
 - b. Shown on the approved site plan,
 - c. Removed within 30 days of occupancy of the last building on the site, or after a period of 90 consecutive days where construction has ceased on the site.
 - d. Provide accessible parking, and receive all applicable building permits.
10. Signs shall be in accordance with the Township Ordinances as set forth in DR §526 except as follows:
 - a. One permanent monument-type entry sign is permitted per entrance, as provided below:
 - i. The entire sign base is in contact with the ground, utilizing a base or structural frame of stone, brick, or other material that is harmonious in architectural style and material to the existing principal building(s) on site.
 - ii. Maximum sign face area: 50 square feet.
 - iii. Maximum sign height: 12 feet.
 - iv. Minimum setback: five feet from all property lines, and may be permitted within the Buffers.
 - v. Signs may only be externally illuminated by ground lights directed at the sign and in compliance with Chapter DR.
 - vi. Temporary Signs are permitted in accordance with the **Temporary Model Home, Trailer, and Signage Exhibit**, prepared by vhb Engineers, attached as


Appendix B of this Plan, but shall comply with the setback requirements of Chapter DR. Banner or flag type signs may be permitted, subject to approval by the Planning Board with respect to the number, sizes and locations.

- 11.A buffer of 50' shall be provided around the perimeter of the site. No buildings, fee simple lots, stormwater management areas, or other structures may be located in these buffers, aside from access drives, walking trails, emergency access and signage. See Buffer images below.
 - a) All perimeter buffers shall contain berming of at least 4' in height, unless prevented by the presence of wetlands or Flood Hazard Areas. Where berms are not provided, increased evergreen tree plantings shall be provided to achieve the buffering objective.
 - b) Berms shall have gently curving, naturalistic forms with vertical and horizontal variation as shown in the images below. Berm slopes shall not exceed 3:1, with an average slope of between 4:1 and 5:1.
 - c) Buffers shall include a variety of plant materials with a predominance of evergreen trees planted generally along the ridge of the berms to maximize the buffer screening. The planting requirements are set forth under the "Landscaping" section below.
 - d) Stormwater management may be provided in the buffer adjacent to the regional trail, provided that a minimum planting area of 10' is maintained.


Perimeter Buffer Concept



Perimeter Buffer Section




Perimeter Buffer Enlargement




12. Community Open Space and Recreation Facilities shall be provided to include walking paths and sidewalks, benches, pet waste containers, and common Amenity Areas. See images below.
- a) The Amenity area for the Townhouse and Single Family Component shall include an 18'x18' shade pavilion, children's play area with fencing, pickleball courts, benches, picnic tables, grills, bike racks, and accent plantings, as shown on the figure below. The final location and configuration shall reflect the final site layout, to be approved at the time of Site Plan Approval.
 - b) Each Affordable Townhouse building shall include its own Amenity area, located within 100' of the building it serves, to include a 14'x14' shade pavilion, benches, picnic tables, a grill, and accent plantings, as shown on the figure below. Where an Affordable Townhouse Building is adjacent to another Affordable Townhouse Building, the Amenity Area may be shared between each building, subject to Planning Board Approval. The final location and configuration shall reflect the final site layout, to be approved at the time of Site Plan Approval.
 - c) The Senior Twin Component shall include its own Amenity area similar in size and scope to the Affordable Townhouse building Amenity area.

Community Amenity Area Concept



Affordable Townhouse & Senior Twin Amenity Area Concept



13. The provision of a fenced dog walk area, and shared/neighborhood garden areas shall be considered, and determined at the time of Site Plan Approval.
14. The construction of a 10' wide Regional Bike Trail along the eastern portion of the site within the former Railroad Right-of-Way. The constructed Trail and the area of Lot 27 will be dedicated to the Township, or to Burlington County, at the discretion of Medford Township.
 - a) Design and Construction shall comply with the requirements for *Shared Use Paths* and other relevant sections of the most recent edition of the "Guide for the Development of Bicycle Facilities", published by the American Association of State Highway Transportation Officials (AASHTO), currently 2024 edition.
 - b) All materials and construction shall comply with NJDOT construction and material standards.
 - c) Trail width shall be 10'-0' minimum, with 5' wide minimum cleared grass shoulders.
 - d) Trail pavement section shall consist of Dense-Graded Aggregate Base Course (6" minimum thickness) and Hot Mix Asphalt 12.5 H 76 Surface Course, (3" minimum thickness). Additional thickness or use of geotextile may be necessary based on conditions of existing soils.
 - e) Signage and striping shall be provided as necessary for safe operation, warnings, etc. shall comply AASHTO standard.
 - f) Fencing, gates, bollards, etc. shall be provided in a manner that allows safe maintenance access via public rights of way or otherwise provides access easement.

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

g) The sidewalk network within the community should connect to the trail in two locations.

15. The provisions of Open Space and Recreation requirements of Section 609 of the Development Regulations are replaced with the provisions herein.

Site Architecture Elevations

The elevations shall be substantially consistent with the graphic illustrations below. Additional Elevations and Floor Plans are included as Appendix C.

Market Rate Townhomes-

Crofton





Crofton II



Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ



Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ



Taylor





Affordable Townhomes

Olivia



Senior Affordable Twins

Tanner



Single Family











Design and Performance Standards

The following design and performance standards supplement the design and performance standards for the **Zoning District**. In the event of a conflict between the general design and performance standards of the Ordinance and this Redevelopment Plan, this Redevelopment Plan shall govern.

All projects shall be submitted to and approved by the Redevelopment Entity/Township Council prior to any Site Plan or Subdivision Application submitted to the Planning Board. This shall include all materials and colors depicted for all facades of all building types.


General Site Design Standards

1. All streets, parking, sidewalks, water supply, sewer and other related infrastructure shall comply with the NJ Residential Site Improvement Standards.
2. Accessible parking shall be provided in accordance with the NJ Barrier-Free Sub-Code and the Americans with Disabilities Act requirements.
3. Electric Vehicle Charging and Make Ready spaces shall be provided as required by Law. This is particularly noted for the parking areas associated with the Affordable Townhouse common parking areas.
4. Unless located within a building, the location of centralized mail/cluster box units (CBU's) must be shown on the Site Plan in safe, convenient, handicap accessible locations, ideally near common parking areas, noting that the locations are subject to approval by the local postmaster. The siting of these areas should avoid the need for automobiles to stop in travel lanes.
5. The Redeveloper shall comply with all Local, County, NJDEP, Soil District, and all other state and outside agency approvals. Any site layout changes required by outside agencies shall be submitted to the Redevelopment Entity for review and approval relative to consistency with the intent of the redevelopment plan.
6. All Stormwater Management systems shall be designed to comply with the current NJDEP stormwater management regulations, RSIS standards and Township Ordinances, and should incorporate green infrastructure measures as required by the regulations.
7. All soil log/pit excavations and permeability/percolation testing shall be witnessed by the Township Engineer's office, in accordance with Township Ordinances and State Law.
8. The design and installation of all water, sewer and related infrastructure, including water storage if required to meet fire flow and pressure standards, shall comply with all applicable Township Ordinances, County, State and Federal regulations, and shall be approved by the Township Engineer.
9. Pipe Materials shall consist of the following:
 - a. Storm sewer shall be reinforced concrete pipe (RCP) within public right of ways
 - b. Storm sewer shall be high density polyethylene (HDPE) in non-public right of ways, privately owned areas and parking areas, if approved by the Township Engineer.
 - c. Water mains shall be Cement Lined Ductile Iron Pipe (CLDIP)
 - d. Sanitary Sewer (Gravity) shall be polyvinyl chloride pipe (PVC)

- e. Sanitary Force main shall be Ductile Iron Pipe (DIP)
 - f. Approved alternatives may be allowed based on local review authority recommendations or requirements
10. Stormwater Management facilities may not be located within required buffers. Subsurface pipes for conveyance only may cross buffers, provided that the buffering requirement is not impacted.
 11. Stormwater management facilities, are permitted to be located within front yard areas internal to the site. If basin fencing is required, it may also be located within internal front yards, but must be located outside of sight triangles, and may not exceed 4' in height. Fencing colors and materials shall be warm muted earth tones to deemphasize their presence. Materials may include pressure treated lumber or vinyl.
 12. Topsoil may be removed from the project, provided that a sufficient volume of topsoil is retained on site to provide a minimum depth of 6" of topsoil in all lawn and planting areas, and any topsoil removed from the site remains within the municipality. All such calculations shall be provided to an approved by the Township Engineer.
 13. Sidewalks shall be provided continuously along all existing street frontages.
 14. Sidewalks shall conform with Residential Site Improvement Standards (RSIS) and shall be provided along street frontages and shall connect into the sites. Sidewalks shall also connect the various uses and components of the site.
 15. All public sidewalks within rights of way, or on site within easements, shall comply with Public Right of Way Accessibilities Guideline (PROWAG) in all respects, with specific attention called to sidewalk widths and turn around areas.
 16. Pedestrian sidewalks and cross access easements shall be provided where required by the Redevelopment Entity or Planning Board, to provide safe and efficient comprehensive pedestrian circulation throughout the site, and between various components of the site.
 17. Where parking is provided perpendicular adjacent to sidewalks, sidewalks shall be a minimum of six (6) feet wide to provide for vehicle overhang and allow accessibility.
 18. The maintenance of all parking spaces and parking lots, whether on private or common area property, or wholly or partially within a right-of-way, shall be the responsibility of the Homeowners Association, or the owner/management entity in the case of a multi-family rental property.
 19. All yard requirements and limitations shall be set forth in the Homeowner Association documents, which shall be reviewed and approved by the Planning Board and Township professionals.
 20. All trash pick-up shall occur between the hours of 7 AM and 7 PM.
 21. All units with garages shall provide for trash and recyclable storage within garages. The container storage areas may not encroach into required parking spaces.
 22. Common trash receptacles, compactors, and dumpster storage areas shall be provided for all units without garage area. These areas shall be effectively screened by a masonry enclosure, at least 6' in height, finished to complement the principal buildings, as shown in the image below. Enclosures shall be planted where practical to soften the appearance

of the structure. Trash enclosure gates shall be constructed of a metal frame for durability, with a vinyl-fence panel or similar, in colors to complement the building.

Refuse Enclosure Concept



23. Trash enclosures may be permitted within internal front yards, but not within a perimeter buffer.
24. Retaining walls shall be warm, muted earth tone colors to deemphasize their presence. Wall capstones should be noted to be epoxied in place for safety.
25. The colors of all fencing and site amenities shall be coordinated with each other and with the building colors. This includes light poles and fixtures, bike racks, metal fencing, central mail box units, trash enclosure fencing, benches, tables, etc.
26. Complete construction details should be provided for all recreation area facilities and common site furnishings. This should include information to demonstrate compliance with the New Jersey Barrier Free Subcode.
27. Signage alerting leash law and clean-up is required by law. Dog waste stations and accompanying trash cans shall be provided at the recreation areas.
28. Covered bicycle parking shall be provided in conjunction with any units that do not have garages, at a rate of at least 1 bicycle per unit.

The enclosure shall be conveniently located within 100' of the building it serves, and shall have at least three sides, with forms, materials and colors to complement the building it serves. See image below.

Bicycle Parking Enclosure Concept



29. A comprehensive maintenance plan shall be submitted to the Redevelopment Entity/Township Council for approval as a condition of Site Plan approval for all exterior areas. This plan shall identify the maintenance responsibilities and obligations of all entities developing the various site components.
30. Bicycle parking shall be provided in conjunction with all development as determined by the Planning Board.
31. Where any driveway of an attached unit is directly adjacent to a neighboring driveway, a decorative, 12" wide contrasting band of concrete pavers shall be provided to define the separation between the respective driveways at the property line.
32. The Redeveloper shall prepare and submit a detailed phasing plan for the overall construction project for review and approval by the Township, prior to the issuance of building permits or the commencement of any on site demolition or site work, whichever occurs first.
33. Buffering, including fencing and planting is required along the sides of the access drive/road connecting to Church Road, to minimize visual and headlight glare impacts to the abutting properties. The final design to be determined at site plan.

General Building Design Standards

1. All buildings shall be designed to have an attractive, finished appearance from all public spaces and public streets, and shall employ traditional architectural forms, materials and colors that complement the architectural vernacular of the Township, and complement the other buildings on site and in the Redevelopment Area. The rear and side facades shall receive substantially consistent design and material treatments as the front facades.
2. Architecture Elevations and Floor Plans shall be substantially consistent with those provided in this Plan; and shall be approved in concept by the Redevelopment Entity/Township Council prior to any Site Plan or Subdivision Application submitted to the Planning Board, unless waived by the Redevelopment Entity/Township Council. This shall include all materials and colors depicted for all facades, depicted on full building strips.
3. High Visibility Facades/Buildings, as shown on the Concept Plan, shall employ a higher level of design and detailed as shown in the elevation exhibits above, focusing those buildings and facades that will be most visible from adjacent streets and existing residential uses.
4. All elevations of all unit types units should be accurately presented based upon the actual topographic conditions of the site, and should include versions showing any full or partial basements, if proposed. Exposed rear and side foundations of shall be architecturally treated with brick or stone masonry to match the front facades. Full length building strips should also be provided. All elevations shall include variations in siding material and/or color, and the introduction of band boards, and eave returns at gables to reduce visual mass.
5. Buildings shall be designed to avoid straight, unbroken façade lines and roof lines. Facades and rooflines shall have dimensional articulation in the façade or roof plane, not more than every 60 linear feet.
6. Building facades may be constructed of the following materials or approved simulated equivalent: natural or man-made brick and stone, wood, vinyl, or cementitious clapboard or shakes, wood beaded siding, and fiber cement clapboards or shingles.
7. Materials for visible pitched roofs shall be standing seam metal, dimensional asphalt shingle, or slate- either real or simulated.
8. Roof styles may include gable, hip, pent, and shed. Heavier roof styles such as mansard or gambrel (barn) roofs are prohibited.
9. To reduce building mass, pitched roofs should have a minimum average roof slope of 5 feet of rise for 12 feet of run (5:12). Flat roofs or areas of flat roof used for mechanical equipment as above, must be screened from view of public area, driveways, and parking lots. If flat roofs are provided, they will not comprise more than fifty (50) percent of the roof area, and the building will appear to have a full sloped roof when viewed from all sides.
10. All exterior building entrances are to be covered with a canopy, pent roof or other architectural feature; and these features are permitted to encroach into the minimum required yard setbacks as described above.

11. Building façades shall have fenestration and design elements including but not limited to decorative windows, operating windows, louvers, shutters, and/or window trim, to prevent large undifferentiated, façade areas of the same material.
12. Major building entrances shall be defined by architectural elements such as recesses, projected overhangs or similar features, and shall relate to the locations of adjacent buildings on site.
13. All window and door surrounds, corner boards and interfaces with siding materials shall have a minimum of 5/4"x4" nominal Azek or similar trim to complement the façade architecture. Band Boards shall also be 5/4 Azek or similar cellular PVC trim.
14. The garage floor plans should be dimensioned to demonstrate the required 9'x18' clear parking area(s). Nothing may encroach upon parking areas, including stairs, trash and recycling containers, required storage, etc. Stairs shall be shown accurately based upon the topography and the presence of basements, as applicable.
15. The following restrictions should be reflected in the HOA documents, and reflected in the deeds.
 - a. Where garage parking spaces are counted toward the RSIS parking requirements, such garages may not be converted to storage, living space, or any space other than parking.
 - b. No living space, office, den, loft, basement or other building area may be converted to an additional bedroom.
16. All buildings and structures on site shall utilize complementary architectural forms, colors and materials.
17. Building and mechanical equipment, including but not limited to HVAC, meters, grills, elevator cabinets, transformers and satellite dishes, shall be located to be visually shielded from adjacent roadways and properties to the extent allowed by utility companies.
18. Roof mounted mechanical equipment roof shall be screened, and not visible from adjacent sites or roadways.
19. All common pedestrian entryways or lobbies must be prominent, lighted, and separate from service entrances.
20. Architectural design will endeavor to minimize the visual impact of garage doors facing a public or neighborhood street by providing windows and decorative elements, such as but not limited to window, panels and hardware, and muted colors other than white to complement the architecture.

Townhouse Design Standards

1. Affordable Townhouse front and rear facades shall provide offsets of at least 2', at a spacing of not more than two units having the same setback. Market Rate Townhouse facades shall have this offset for every unit.
2. Roof lines shall be varied and shall not include a continuous ridge line for more than two units in a row, with height changes or offsets of not less than 12". The articulation of the roof line shall include gables, dormers, offsets, and similar treatments.
3. At all end unit conditions of multiple unit structures, additional windows, bays, porches, fenestration, turned gables, band boards, and other architectural features shall be

provided to enhance the architectural character of the end wall. This includes the provision of side entry end units with porches.

4. The site plans or architecture plans, as applicable, shall demonstrate adequate areas for the provision or storage of personal items such as bicycles, strollers, etc. of at least 250 Cubic feet per Market Rate unit, and 125 Cubic feet per Affordable unit. This may be accommodated within the units, or within common storage areas.
5. Patios or decks at Market Rate units shall be at least 8'x12' in area. Patios or decks at Affordable units shall be at least 8'x10' in area. Units without door access to a rear yard are exempt from this requirement, provided that common sitting areas are provided within 100' of the building.
6. Upper floor decks are not permitted. If a walkout basement condition is approved as part of the site plan, those units will have a deck at the main living level, above the walkout basement.
7. Deck structures, stairs, railings, decking and visible portions of the support structure shall be detailed to complement the building architecture. All decks shall be in a single style, or two complementary styles to be determined at the time of Site Plan Approval. These standards shall be reflected in the HOA documents.
8. For Townhouse units with rear patios or decks, privacy fencing shall be provided and shall extend 8' to 10' from the rear façade, and may be up to 6' in height above grade.
9. Rear yard unit fencing is permitted for the market rate townhouse units, and may be 5' in height, or up to 6' in height if expressly approved by the Planning Board.
10. No fencing may extend forward of the rear building line for townhouse units.
11. All yard fencing must be one or two complementary styles, in a single muted earth tone color, to complement the architecture. All fences shall be detailed on the Site Plans, and included in the HOA documents.
12. Deer fences are not permitted per §513:F-8.
13. No pools, spas or hot tubs, sheds or other structures are permitted on Townhouse lots.

Senior Twin Design Standards

1. All units shall provide rear yard ground level patios or decks at least 8'x10' in area.

Sustainable Building Practices- All Components

To the extent feasible, sustainable site and building practices are encouraged to reduce a project's dependency upon natural resources. These practices may include, but are not limited to, the following:

1. Orient buildings to maximize solar gain in the winter and shade in the summer; include vegetated wind breaks and sun screens;
2. Where practical, plant native or naturalized vegetation to minimize water, pesticide and herbicide usage and to create foraging opportunities for wildlife;

3. Install operable windows, awnings, shading devices and roof vents to reduce reliance on HVAC units;
4. Maximize daylight in living spaces to reduce reliance on artificial lighting;
5. Maximize building and window insulation to conserve energy and reduce energy costs;
6. Encourage the use of recycled building and site materials and recycle construction debris;
7. Create shaded parking areas to reduce reliance on automotive air conditioning;
8. Create opportunities for bicyclists and pedestrianism to reduce reliance on automobiles including shaded sidewalks, benches, bike lanes and bike racks;
9. All development projects are required to install electric vehicle charging stations, as defined in the LRHL, as required by N.J.S.A. 40A:12A-7(a)(8), which provides for consideration of locations for EV charging infrastructure.

Landscaping

To promote a desirable visual environment through creative techniques and good civic design and arrangements; and to promote the conservation of open space and valuable natural resources in the Township, all redevelopment shall comply with the landscape standards set forth in **Chapter DR- Development Regulations**, and the standards below, or provide a more appropriate design relative to the specific aspects of a particular site to be approved by the Planning Board.

1. All areas shall be designed to enhance the visual quality of the site; provide safe vehicular and pedestrian circulation; protect against potential natural and man-made hazards in a manner which will promote the public health, safety and general welfare.
2. The use of native and naturalized vegetation shall be maximized to reduce water consumption, pesticide and herbicide usage and to create habitat and foraging opportunities for wildlife.
3. The provisions of Section 520.C. relating to landscaping in parking areas is not applicable to the redevelopment area.
4. Shade trees shall be planted around the perimeter of parking areas at a rate of 1 tree per 10 spaces.
5. Buffers shall include a variety of plant materials with a predominance of evergreen trees planted generally along the ridge of the berms to maximize the buffer screening. The planting requirements are set forth under the “Landscaping” section below.

Buffering of adjacent uses, roadways and zones is critical and includes those residential properties adjacent to the site as described above and perimeter road buffers.

These buffers shall include berms with naturalized masses of predominantly evergreen trees, with layers of evergreen and deciduous shrubs, as well as ornamental and shade trees. Per each 100 linear feet of buffer, the following shall be provided:

<u>Plant Type</u>	<u>Required/100 LF</u>	<u>Size</u>
Evergreen Trees	8	6-8' Ht.; (25% shall be 8-10' Ht.)
Shade Trees	2	2.5" Caliper
Ornamental Trees	3	8-10' Ht.
Evergreen Shrubs	25	24" Ht.
Deciduous Shrubs	15	24" Ht.

These quantities may be reduced where adequate evergreen vegetation exists to meet the buffering objective, subject to approval by the Planning Board.

Where berming is not permitted due to the presence of Freshwater Wetlands and/or Transition Areas, a modified buffer planting of native tree and shrub plantings is required, consistent with NJDEP regulations. If not permitted by NJDEP, a modified landscape buffer configuration and planting design must be provided to achieve the buffering intent.

6. Street trees, parking lot trees and trees near walkways shall be single trunk, full, and uniform specimens, and shall have branching not lower than 6' above grade to avoid conflicts with pedestrians, vehicles, or signs. Trees within any sight triangle shall be pruned to a 7' branching height, and such locations shall be approved by the Board Engineer.
7. 6" of topsoil shall be provided in all lawn and planting areas.
8. All dead or severely declining plants shall be replanted within the next growing season during the performance and maintenance bond periods.
9. Individual lot landscaping plans shall be provided on the site development plans. The number of trees and shrubs and size of material provided shall be identified as part of the site plan review on a landscape plan, provided as follows:
 - a. Single Family Lot- 1 shade tree, 1 ornamental tree, 15 shrubs, and 9 perennials
 - b. Market Rate Townhouse Lot- 1 shade or ornamental tree, 7 shrubs, and 9 perennials
 - c. Senior Twin Lot- 1 shade tree, 1 ornamental tree, 12 shrubs, and 9 perennials
 - d. For Affordable units located on a common lot, shade or ornamental trees, shrubs, and perennials shall be provided around the building at a similar intensity to the Market Rate Townhouse lot plantings set forth above.
10. Maintenance of landscape areas is a crucial part of any land development and must be addressed for all exterior areas of the Redevelopment Area. Specifications for the perpetual maintenance of all outdoor areas on site to assure a safe and attractive environment and to promote healthy growth of all plant materials shall be provided. This shall include identification of the parties responsible for said maintenance.
11. All common yard areas shall be maintained by the Homeowners Association or management entity, not individual property owners.
12. All plants shall be planted in accordance with appropriate Planting Details and notes, to ensure the proper installation, survival and growth of all plantings.
13. Tree varieties should be utilized which exhibit desirable characteristics, such as full symmetrical form, deep noninvasive root system and tolerance of potential drought conditions and road salt.

14. No tree shall interfere with utilities, roadways, sidewalks, street or parking lot lighting, sight distances, driveway aprons or fire hydrants.
15. Replacement trees shall conform to the type of originally planted tree in a given area, provided that, if any deviation is anticipated, it must be done only with the written permission from the Township Planner/Landscape Architect.
16. All plant material and landscaping shall be guaranteed under a performance bond, and a 2 year maintenance bond.
17. Recently adopted fire code revisions, (NJAC 305.6), prohibit the use of combustible landscape materials/mulch within 18" of certain buildings and structures. The plans should address compliance with notes and/or details.
18. All Buffers, and unit front and side yards shall be sodded, as well as all areas within 20' of roads, driveways, parking areas and recreation amenities. Rear yards and other common areas may be seeded.
19. Automatic underground irrigation systems should be considered for highly visible planted areas of the site, such as vehicular access points and office entrance areas. All sodded areas shall be irrigated. Irrigation systems shall be designed to maximize water usage efficiency by minimizing evaporation and overspray. Rain sensors or soil moisture sensors are required to conserve water by reducing the unnecessary over watering of plantings.
20. Agricultural field areas including wetlands, buffer/transition areas, and other regulated areas that are to remain undeveloped shall be overseeded with native grass and wildflower meadow species that will be beneficial to local and migratory songbird species, pollinators and other species, to the extent permitted by regulatory agencies.

Detailed maintenance and establishment specifications shall be provided at the time of site plan approval. The design shall also include the installation of 1" caliper tree whips/saplings and 24" tubelings, in equal proportions, at a rate of 1 tree per 1,000 SF of undeveloped area to be established as meadow. These trees shall be planted in naturalized clusters.

Lighting

1. All areas shall receive adequate but not excessive illumination in accordance with applicable Township Ordinances, and IESNA recommendations.
2. All exterior lighting shall be full cut-off or dark sky compliant fixtures, except for accent lighting expressly approved by the Planning Board.
3. All light fixtures shall have a correlated color temperature of 3,000° Kelvin, or less. LED fixtures are permitted.
4. Pole mounted and building mounted lights may not exceed 30 feet in height.
5. Lighting should be reduced or turned off overnight, or reduced to security levels where practicable. This does not apply to street lighting, or residential parking areas.
6. Lighting shall not exceed 0.0 foot-candles off site at any property line in common with an adjacent residential use or residential Zoning District.

VII. Affordable Housing, Property Acquisition, & Relocation

Affordable Housing

There are no existing or proposed affordable housing units to be removed in conjunction with this Redevelopment Plan, so no replacement plan is required.

Identification of Proposed Property Acquisitions

The Redevelopment Area has been determined to be a *Redevelopment Area, without Condemnation*. There are no proposed property acquisitions contemplated or permitted.

Temporary/ Permanent Resident Relocation

The Redevelopment Area is not occupied by residents or housing of any type. Therefore, no resident relocation is necessary.

VIII. Plan Relationship to Definitive Local Objectives

Contiguous Municipalities

The municipalities contiguous to Medford Township include the Townships of Evesham, Mt. Laurel, Lumberton, Southampton, Tabernacle, Shamong, and Waterford, and the Borough of Medford Lakes, which is surrounded entirely by Medford.

The Redevelopment Area is located within the northeastern portion of the Township, over 1.4 miles from the Southampton Township border, and nearly 1 mile from Lumberton Township along Route 541. The implementation of this Redevelopment Plan is not anticipated to have any significant adverse impact on the adjacent municipalities.

To the contrary, the Redevelopment Plan satisfies Medford's constitutional obligation to provide their fair share of the *region's* affordable housing needs.

Burlington County

Burlington County does not have a county master plan, but provides corridor studies, farmland preservation and open space plans, none of which are applicable to the Redevelopment Area. The County has generally relied upon the New Jersey State Development and Redevelopment Plan and the Pinelands CMP for its land use policy for the county as a whole. Burlington County is the largest county in the State of New Jersey, consisting of 819 square miles.

It should be noted that the Redevelopment Area has frontage on a County Road, and all projects must comply with County standards for development, as applicable, and will require approval from Burlington County.

NJ State Plan and Smart Growth Planning Areas

According to the 2025 State Development and Redevelopment Plan (SDRP) the Redevelopment Area is located within the Rural (PA4) Planning Area. According to the SDRP, the intent of the Rural Planning Area (PA4) is to:

- maintain the Environs as large contiguous areas of farmland, open space, and forested areas;
- enhance habitats and sensitive lands;
- accommodate growth in Centers, excluding flood prone areas;
- reverse auto-oriented patterns of development;
- promote a viable agricultural or forestry industry;
- revitalize cities, towns, and other traditional settlements;
- protect, enhance, and support local agricultural economies; and
- confine programmed sewers and public water services to Centers, except where public health is at stake.

IX. Administrative and Procedural Requirements

Compliance with Affordable Housing Obligation

This Redevelopment Plan provides for the construction of 36 Age-Restricted, Affordable Twin Dwelling Units, and 12 Affordable Rental, 3-Bedroom Stacked Townhouse Dwelling Units.

All affordable housing units will be designed, developed, constructed, administered and restricted in accordance with the Fair Housing Act, N.J.S.A. 52:27D-301 et seq., applicable Council on Affordable Housing regulations, any orders of the court including a Judgement of Compliance and Repose Order (“JOR Order”) and any amendments to same, the Township’s Affordable Housing Ordinance, the requirements of the Uniform Housing Affordability Controls (‘UHAC’) at N.J.A.C. 5:80-26.1 et seq. and any other applicable law. These requirements include, but are not limited to, phasing, affirmative marketing, pricing, bedroom distribution, low/mod split, affordability controls and long-term administration by a qualified and experienced Administrative Agent.

These affordable housing provisions shall be expressly set forth in a Redevelopment Agreement.

Amending the Redevelopment Plan

Upon compliance with the requirements of applicable law, the Governing Body may amend, revise, or modify this Redevelopment Plan, as circumstances may make such changes appropriate, following the required procedures of the LHRL.

Duration of the Redevelopment Plan

The Redevelopment Plan, which may be amended, shall be in full force and effect for a period of thirty (30) years from the date of approval of the Redevelopment Plan.

Redevelopment Entity

The Township Council of the Township of Medford shall serve as the redevelopment entity.

Redeveloper Selection

The Township Council/Redevelopment Entity may designate qualified redeveloper(s) to undertake work to implement the provisions of this Redevelopment Plan, in accordance with the provisions set forth in the Local Redevelopment and Housing Law (LRHL).

Redevelopment Plan Effectuation

Upon the adoption of this redevelopment plan pursuant to section 7 of P.L.1992, c.79 (C.40A:12A-7), as set forth in 40A:12A-8 Effectuation of development plan; the Township Council/Redevelopment Entity may proceed with the clearance, replanning, development and redevelopment of the area designated in that plan. In order to carry out and effectuate the purposes of this act and the terms of the redevelopment plan, the Township Council /Redevelopment Entity may:

- a. Undertake redevelopment projects, and for this purpose issue bonds in accordance with the provisions of section 29 of P.L.1992, c.79 (C.40A:12A-29).
- b. Acquire property pursuant to subsection i. of section 22 of P.L.1992, c.79 (C.40A:12A-22).
- c. As this is a redevelopment area, without condemnations, the powers of Eminent Domain authorized under the LRHL and Eminent Domain Act are not available.
- d. Clear any area owned or acquired and install, construct or reconstruct streets, facilities, utilities, and site improvements essential to the preparation of sites for use in accordance with the redevelopment plan.
- e. Prepare or arrange by contract for the provision of professional services and the preparation of plans by registered architects, licensed professional engineers or planners, or other consultants for the carrying out of redevelopment projects.
- f. Arrange or contract with public agencies or redevelopers for the planning, replanning, construction, or undertaking of any project or redevelopment work, or any part thereof; negotiate and collect revenue from a redeveloper to defray the costs of the redevelopment entity, including where applicable the costs incurred in conjunction with bonds, notes or other obligations issued by the redevelopment entity, and to secure payment of such revenue; as part of any such arrangement or contract, provide for extension of credit, or making of loans, to redevelopers to finance any project or redevelopment work, or upon a finding that the project or redevelopment work would not be undertaken but for the provision of financial assistance, or would not be undertaken in its intended scope without the provision of financial assistance, provide as part of an arrangement or contract for capital grants to redevelopers; and arrange or contract with public agencies or redevelopers for the opening, grading or closing of streets, roads, roadways, alleys, or other places or for the furnishing of facilities or for the acquisition by such agency of property options or property rights or for the furnishing of property or services in connection with a redevelopment area.
- g. Except with regard to property subject to the requirements of P.L.2008, c.65 (C.40A:5-14.2 et al.), lease or convey property or improvements to any other party pursuant to this section, without public bidding and at such prices and upon such terms as it deems reasonable, provided that the lease or conveyance is made in conjunction with a redevelopment plan, notwithstanding the provisions of any law, rule, or regulation to the contrary.

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

- h. Enter upon any building or property in any redevelopment area in order to conduct investigations or make surveys, sounding or test borings necessary to carry out the purposes of this act.
- i. Arrange or contract with a public agency for the relocation, pursuant to the "Relocation Assistance Law of 1967," P.L.1967, c.79 (C.52:31B-1 et seq.) and the "Relocation Assistance Act," P.L.1971, c.362 (C.20:4-1 et seq.), of residents, industry or commerce displaced from a redevelopment area.
- j. Make, consistent with the redevelopment plan: (1) plans for carrying out a program of voluntary repair and rehabilitation of buildings and improvements; and (2) plans for the enforcement of laws, codes, and regulations relating to the use and occupancy of buildings and improvements, and to the compulsory repair, rehabilitation, demolition, or removal of buildings and improvements.
- k. Request that the planning board recommend and governing body designate particular areas as being in need of redevelopment or rehabilitation in accordance with the provisions of this act and make recommendations for the redevelopment or rehabilitation of such areas.
- l. Study the recommendations of the planning board or governing body for redevelopment of the area.
- m. Publish and disseminate information concerning any redevelopment area, plan or project.
- n. Do all things necessary or convenient to carry out its powers.

Redevelopment Agreement(s)

As permitted by the Local Redevelopment and Housing Law (LRHL), the Redevelopment Entity shall enter into a Redevelopment Agreement with the designated Redeveloper(s), which Agreement ***may include*** negotiation of long-term financial agreements and/or tax abatement, and shall be consistent with the provisions of at 40A:12A-8, as follows:

- a. All agreements, leases, deeds and other instruments from or between a municipality or redevelopment entity and to or with a redeveloper shall contain a covenant running with the land requiring that the owner shall construct only the uses established in the current redevelopment plan; a provision requiring the redeveloper to begin the building of the improvements for those uses within a period of time which the municipality or redevelopment entity fixes as reasonable; a provision that the redeveloper shall be without power to sell, lease or otherwise transfer the redevelopment area or project, or any part thereof, without the written consent of the municipality or redevelopment entity; a provision that upon completion of the required improvements, the conditions determined to exist at the time the area was determined to be in need of redevelopment shall be deemed to no longer exist, and the land and improvements thereon shall no longer be subject to eminent domain as a result of those determinations; and any other covenants, provisions and continuing controls as may be deemed necessary to effectuate the purposes of this act. The aforesaid covenants, provisions and controls shall be deemed satisfied upon termination of the agreements and covenants entered into by the redeveloper to construct the improvements and to perform the redevelopment. The rights of any third party acquired prior to termination of the agreements, including, but not limited to, any tax exemption or

Redevelopment Plan: Trollinger-Stonebridge Medford Township, NJ

abatement granted pursuant to law, shall not be negatively affected by termination and satisfaction of the covenants.

- b. A lease to a redeveloper may provide that all improvements shall become the property of the municipality or redevelopment entity. The execution of a lease with that provision shall not impose upon the municipality or redevelopment entity any liability for the financing, construction, management or operation of any redevelopment project, or any part thereof.

Severability

If any provision of this Redevelopment Plan shall be adjudged by the courts to be invalid, such adjudications shall apply only to the provision so adjudged and the remainder of the Plan shall be deemed valid and effective.

Appendices- Inserted on the Following Pages.

Appendix A- Concept 15 Plan, prepared by vhb Engineers, dated February 26, 2026.

Appendix B- Temporary Model Home, Trailer, and Signage Exhibit, prepared by vhb Engineers, dated February 26, 2026.

Appendix C- Building Elevations and Floor Plans, prepared by DR Horton/Wade Architecture & Holliday Architects, bearing various dates.



Know what's below.
Call before you dig.



NO.	DATE	ISSUE OR REVISION	BY
4	02.25.2026	REV. PER ADDITIONAL COMMENTS	CGT
3	02.24.2026	REV. PER ADDITIONAL COMMENTS	CGT
2	02.13.2026	REV. PER ADDITIONAL COMMENTS	BLK
1	02.04.2026	REV. PER ADDITIONAL COMMENTS	BLK

REVISIONS

PROJECT:
STONEBRIDGE



LOCATION:
BLOCK 302, LOTS 14, 26, 27 & 49
MEDFORD TOWNSHIP
BURLINGTON COUNTY, NJ

DRAWING TITLE:
CONCEPT 26


JOSEPH PANRAHAN
PROFESSIONAL ENGINEER
LICENSE NUMBER 40339
NJ LICENSE NUMBER 76067
CT LICENSE NUMBER 43422
CT LICENSE NUMBER 28350

DRAWN BY: MGM | CHECKED BY: JDH | DRAWING NUMBER:
SCALE: 1" = 150'
JOB NUMBER: 23125 | DATE: 01.21.26 | SHEET 1 OF 1

- 300 Total Units
- 36 Fee Simple Affordable Active Adult Twin Lots
45' x 120' Active-Twin Lots
- 139 Fee Simple Market Rate Single Family Lots With
Optional Basement
60' x 120' Single Family Lots
- 113 Fee Simple Market Rate 'Crofton' Townhouses With
Optional Basement
2-Story, 28' x 50' 4-Bedroom Townhouses With Optional Deck/Patio
- 12 Affordable Rental Stacked Condo 'Olivia' Units
2-Story Building, 24' x 54' (3) Bedroom Family Rental Units
- HIGH VISIBILITY FACADES
- Layout Design
50' Perimeter Buffer
25' Front Setback
- Base Information
Township Tax maps
Aerial image provided by BingMaps




NOTE:
THIS PLAN IS FOR CONCEPTUAL PLANNING PURPOSES ONLY AND IS SUBJECT TO DUE DILIGENCE, DETAILED ZONING REVIEW AND SITE PLANNING DESIGN PROCESS INCLUDING, BUT NOT LIMITED TO UTILITY, DRAINAGE, ENVIRONMENTAL, SURVEY, AND GEOTECHNICAL INVESTIGATIONS, ETC.




FRONT ELEVATION "C"

FRONT ELEVATION "D"



UN-FINISHED BASEMENT FLOOR PLAN



FINISHED BASEMENT FLOOR PLAN



WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
D.MAYA
DATE:
12/31/2025
PROJECT NO.
MN01
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"


HOUSE NAME:
STONEBRIDGE ESTATE MONTEREY
DRAWING TITLE
BASEMENT FOUNDATION
PLANS

SHEET No.
A.3.2




FIRST FLOOR PLAN






SECOND FLOOR PLAN
W/ BEDROOM #3 AND LOFT




SECOND FLOOR PLAN
W/ BEDROOM #3 AND OPT. BEDROOM #4

DONE TO COMPLY WITH ALL
IS.



FINISHED BASMENT LEVEL FLOOR PLAN



BASMENT LEVEL FLOOR PLAN


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
FLOOR PLANS

SHEET No.
A.1



FIRST FLOOR PLAN
W/ BASMENT



FIRST FLOOR PLAN
W/ OPT. 2' GARAGE EXTENSION
W/ BASEMENT COND.


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
FLOOR PLANS


SHEET No.
A.3



SECOND FLOOR PLAN



FRONT ELEVATION "B3"



FRONT ELEVATION "C3"

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638


D.R. HORTON
America's Builder

DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-

11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
FRONT ELEVATIONS

SHEET No.
A.2.1



FRONT ELEVATION "D5"
 HI-VIZ W/ BASEMENT


WADE
 ARCHITECTURE
 HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
 WADE
 DATE:
 02/17/2026
 PROJECT NO.
 -
 11 X 17 SCALE
 1/8" = 1'-0"
 24 X 36 SCALE
 1/4" = 1'-0"

HOUSE NAME:
 STONEBRIDGE ESTATE- MONTGLER DESIGN
 DRAWING TITLE
 FRONT ELEVATIONS



SHEET No.
 A.2.1



REAR ELEVATION
HI-VIZ W/ IN-GROUND BASEMENT



REAR ELEVATION
W/ WALK-OUT. BASEMENT






DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTCLER DESIGN
DRAWING TITLE
REAR ELEVATIONS

SHEET No.
A.2.2

2/26/2026




WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
HI-VIZ REAR SIDE
ELEVATIONS

SHEET No.
A.2.3



REAR ELEVATION
HI - VIZ IN-GROUND BASEMENT



REAR ELEVATION
HI-VIZ W/ WALKOUT. BASEMENT


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTICLER DESIGN
DRAWING TITLE
REAR ELEVATIONS

SHEET No.
A.2.4



REAR ELEVATION
W/ IN-GROUND BASEMENT



REAR ELEVATION
W/ WALK-OUT. BASEMENT


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
STANDARD REAR
ELEVATIONS

SHEET No.
A.2.J



LEFT SIDE ELEVATION
WALK-OUT BASEMENT



RIGHT SIDE ELEVATION
WALK-OUT BASEMENT


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
STANDARD SIDE
ELEVATIONS

SHEET No.
A.2.6



RIGHT SIDE ELEVATION
WALK-OUT BASEMENT HI-VIZ



LEFT SIDE ELEVATION
WALK-OUT BASEMENT HI-VIZ


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder



DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
HI VIZ SIDE ELEVATIONS

SHEET No.
A.2.7



RIGHT SIDE ELEVATION
WALK-OUT BASEMENT HI-VIZ



LEFT SIDE ELEVATION "D5"
HI-VIZ - WALK-OUT BASEMENT


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE- MONTGLER DESIGN
DRAWING TITLE
HI VIZ SIDE ELEVATIONS


SHEET No.
A.2.8



RIGHT SIDE ELEVATION
IN-GROUND BASEMENT HI-VIZ



LEFT SIDE ELEVATION
IN-GROUND BASEMENT HI-VIZ



WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638


D·R·HORION
America's Builder

DRAWN BY: WADE
DATE: 02/17/2026
PROJECT NO. -
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME: STONEBRIDGE ESTATE- MONTICLER DESIGN
DRAWING TITLE: HI VIZ SIDE ELEVATIONS

SHEET No. **A.2.9**

2/26/2026



LEFT SIDE ELEVATION "D5"
 HI-VIZ - IN-GROUND BASEMENT


WADE
 ARCHITECTURE
 HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
 WADE
 DATE:
 02/17/2026
 PROJECT NO.
 -
 11 X 17 SCALE
 1/8" = 1'-0"
 24 X 36 SCALE
 1/4" = 1'-0"

HOUSE NAME:
 STONEBRIDGE ESTATE- MONTGLER DESIGN
 DRAWING TITLE
 HI VIZ SIDE ELEVATIONS

SHEET No.
 A.2.10



FINISHED WALK-OUT BASEMENT FLOOR PLAN



UNFINISHED BASEMENT FLOOR PLAN

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638


D.R. HORTON
America's Builder

DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"


HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
FLOOR PLANS

SHEET No.
-

2/26/2026



SECOND FLOOR PLAN



SECOND FLOOR PLAN
W/ OPT LOFT


WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder


DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
FLOOR PLANS


SHEET No.
10



FRONT ELEVATION "D5"




FRONT ELEVATION "D3"




FRONT ELEVATION "H5"




FRONT ELEVATION "H3"







FRONT ELEVATION "E5"




FRONT ELEVATION "E3"



REAR ELEVATION
 HI- VIZ W/ ELEVS. "D" & "E"
 W/ IN-GROUND BASEMENT



REAR ELEVATION "H"
 HI-VIZ W/ IN-GROUND BASEMENT



WADE
 ARCHITECTURE
 HAGERSTOWN, MD 240-452-4638


D.R. HORION
America's Builder

DRAWN BY:
 WADE
 DATE:
 02/17/2026
 PROJECT NO.
 -
 11 X 17 SCALE
 1/8" = 1'-0"
 24 X 36 SCALE
 1/4" = 1'-0"


HOUSE NAME:
 STONEBRIDGE ESTATE - HAMPSHIRE
 DRAWING TITLE
 HI- VIZ REAR ELEVATIONS

SHEET No.
 A.2.4


2/26/2026





REAR ELEVATION
HI-VIZ W/ ELEVS. "D" & "E"
W/ WALK-OUT BASEMENT




REAR ELEVATION "H"
HI-VIZ W/ OPT. WALK-OUT BASEMENT
W/ OPT. CRAWL SPACE



REAR ELEVATION
 W/ ELEVS. "D" "H" & "E"
 W/ WALK-OUT BASEMENT



REAR ELEVATION
 W/ ELEVS. "D", "H" & "E"
 W/ IN-GROUND BASEMENT



WADE
 ARCHITECTURE
 HAGERSTOWN, MD 240-452-4638


D.R. HORION
America's Builder

DRAWN BY:
 WADE
 DATE:
 02/17/2026
 PROJECT NO.
 -
 11 X 17 SCALE
 1/8" = 1'-0"
 24 X 36 SCALE
 1/4" = 1'-0"


HOUSE NAME:
 STONEBRIDGE ESTATE - HAMPSHIRE
 DRAWING TITLE
 STANDARD REAR
 ELEVATIONS

SHEET No.
 A.2.6


2/26/2026




LEFT SIDE ELEVATION "D3" & "D5"
HI-VIZ




LEFT SIDE ELEVATION "H3"
HI-VIZ



LEFT SIDE ELEVATION "E3" & E5
HI-VIZ



RIGHT SIDE ELEVATION "E3" & "E5"
HI-VIZ



WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638


D.R. HORION
America's Builder

DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"


HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
HI-VIZ SIDE
ELEVATIONS "E"

SHEET No.
A.2.8


2/26/2026



LEFT SIDE ELEVATION "E"



RIGHT SIDE ELEVATION "E"



WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder

DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
STANDARD SIDE
ELEVATIONS "E"

SHEET No.
A.2.9


2/26/2026




DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
STANDARD SIDE
ELEVATIONS "D"


SHEET No.
A.2.10




LEFT SIDE ELEVATION "D"



RIGHT SIDE ELEVATION "D"



LEFT SIDE ELEVATION "H"



RIGHT SIDE ELEVATION "H"

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder

DRAWN BY:
WADE
DATE:
02/17/2026
PROJECT NO.
-
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
STONEBRIDGE ESTATE - HAMPSHIRE
DRAWING TITLE
STANDARD SIDE
ELEVATIONS "H"

SHEET No.
A.2.11


2/26/2026

28-ft Wide Twin Units

1-Story, 2-Bedroom




Elevation #1 and #1a



CLIENT:



Tanner at Trollinger
Medford, Burlington County, New Jersey 08055



HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737

3212 Brigantine Boulevard
BRIGANTINE, NJ 08203
609.953.5373
FAX: 609.953.5737

REVISIONS:			SHEET TITLE:	
1	12/19/25	Color Changes and Revisions	28 Foot Wide Twin Units	
2	01/14/26	Elevation 2 & 2a	Perspectives	
3	01/16/26	Floor Plans	SCALE: AS NOTED	SHEET NO.
4	01/20/26	High Vis. Rear Elev. Revisions	PROJ. NO.: DRH-25006	SK-1
5	02/13/26	Elevation Revisions	DATE: December 9, 2024	



Side Elevation - High Visibility

Scale: 1/8" = 1'-0"



Rear Elevation - High Visibility

Scale: 1/8" = 1'-0"



Typ. Rear Elevation

Scale: 1/8" = 1'-0"



Typ. Side Elevation

Scale: 1/8" = 1'-0"



Front Elevation


Scale: 1/4" = 1'-0"

- Highest Roof
- Asphalt Roof Shingles
- Dormer
- Mid-Point of Highest Roof
- Aluminum Wrapped Trim Surrounds
- Vinyl Shake Siding
- Asphalt Roof Shingles
- Aluminum Wrapped Fascia & Frieze Boards
- Top of Plate
- Window Heads
- Horizontal Vinyl Siding
- Panel Shutters
- Vinyl Corner Boards
- Manufactured Brick Veneer
- First Floor
- Average Grade


CLIENT:



Tanner at Trollinger
Medford, Burlington County, New Jersey 08055



HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737




REVISIONS:			SHEET TITLE:	
1	12/19/25	Color Changes and Revisions	28 Foot Wide Twin Units 1-Story Elevations	
2	01/14/26	Elevation 2 & 2a	SCALE:	AS NOTED
3	01/16/26	Floor Plans	PROJ. NO.:	DRH-25006
4	01/20/26	High Vis. Rear Elev. Revisions	DATE:	December 9, 2024
5	02/13/26	Elevation Revisions	SK-2	

28-ft Wide Twin Units

1-Story, 2-Bedroom




Elevation #2 and #2a



CLIENT:



Tanner at Trollinger
Medford, Burlington County, New Jersey 08055



HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737

3212 Brigantine Boulevard
BRIGANTINE, NJ 08203
609.953.5373
FAX: 609.953.5737

REVISIONS:			SHEET TITLE:	
1	12/19/25	Color Changes and Revisions	28 Foot Wide Twin Units Perspectives	
2	01/14/26	Elevation 2 & 2a	SCALE:	AS NOTED
3	01/16/26	Floor Plans	PROJ. NO.:	DRH-25006
4	01/20/26	High Vis. Rear Elev. Revisions	DATE:	December 9, 2024
5	02/13/26	Elevation Revisions	SK-3	



Side Elevation - High Visibility

Scale: 1/8" = 1'-0"



Rear Elevation - High Visibility

Scale: 1/8" = 1'-0"



Typ. Rear Elevation

Scale: 1/8" = 1'-0"



Typ. Side Elevation

Scale: 1/8" = 1'-0"



Front Elevation


Scale: 1/4" = 1'-0"

- Highest Roof
- Asphalt Roof Shingles
- Dormer
- Mid-Point of Highest Roof
- Aluminum Wrapped Trim Surrounds
- Vinyl Shake Siding
- Asphalt Roof Shingles
- Aluminum Wrapped Fascia & Frieze Boards
- Top of Plate
- Window Heads
- Horizontal Vinyl Siding
- Panel Shutters
- Vinyl Corner Boards
- Manufactured Brick Veneer
- First Floor
- Average Grade


CLIENT:




Tanner at Trollinger
Medford, Burlington County, New Jersey 08055



HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737




REVISIONS:			SHEET TITLE:	
1	12/19/25	Color Changes and Revisions	28 Foot Wide Twin Units 1-Story Elevations	
2	01/14/26	Elevation 2 & 2a	SCALE:	AS NOTED
3	01/16/26	Floor Plans	PROJ. NO.:	DRH-25006
4	01/20/26	High Vis. Rear Elev. Revisions	DATE:	December 9, 2024
5	02/13/26	Elevation Revisions	SK-4	




Building Plan Elev. 1 / 1a (COAH)

Scale: 1/8" = 1'-0"



Building Plan Elev. 2 / 2a (COAH)

Scale: 1/8" = 1'-0"



First Floor Plan (COAH)

Scale: 1/4" = 1'-0"

Area Calculations

Side-Entry, 1-Story Unit
Elevations 1/1a & 2a

Total Living: 1,151 sq ft
1-Car Garage: 293 sq ft

Side-Entry, 1-Story Unit
Elevation 2

Total Living: 1,151 sq ft
1-Car Garage: 319 sq ft

CLIENT:



Tanner at Trollinger
Medford, Burlington County, New Jersey 08055




HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737

REVISIONS:			SHEET TITLE:	
1	12/19/25	Color Changes and Revisions	28 Foot Wide Twin Units 1-Story Elevations	
2	01/14/26	Elevation 2 & 2a	SCALE:	AS NOTED
3	01/16/26	Floor Plans	PROJ. NO.:	DRH-25006
4	01/20/26	High Vis. Rear Elev. Revisions	DATE:	December 9, 2024
5	02/13/26	Elevation Revisions	SK-5	



DRHORTON.COM

D.R. Horton is equal housing opportunity builder. Windows per plan can vary. With basement foundations, water heaters and HVAC systems will be relocated from the first or second floors, as specified per plan. All pricing, included features, terms, availability and amenities, are subject to change at any time without notice or obligation. Elevations and exterior materials may vary. Square footages, measurements and dimensions are approximate and will vary based on foundation type and options selected. Pictures, artist renderings, photographs, colors, features, and sizes are for illustration purposes only and will vary from the homes as built. Options and upgrades are available at an additional cost and are subject to availability and construction cut-off dates




END UNIT CONDITION
 ALT. STAIRWELL

FIRST FLOOR PLAN



4'-0" CROFTON T3B3 (HI-VIZ) (RIGHT-HAND) CROFTON U3B3 (HI-VIZ) (RIGHT-HAND) CROFTON S3B3 (HI-VIZ) (RIGHT-HAND) CROFTON U3B3 (HI-VIZ) (RIGHT-HAND) CROFTON T3B3 (HI-VIZ) (LEFT-HAND) 4'-0"



CROFTON || LOT X RIGHT

CROFTON || LOT X RIGHT

CROFTON || LOT X RIGHT

CROFTON || LOT X RIGHT

CROFTON || LOT X LEFT

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D.R. HORTON
America's Builder

DRAWN BY: WADE
DATE: 02.10.26
PROJECT NO. ---
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME: TDG PARK VIEW/EPS MEDFORD NJ
DRAWING TITLE: CROFTON II-BUILDING STRIP W/ BSMT HI-VIZ ELE. & PLAN

SHEET No.
3A



REAR ELEVATION (HI-VIZ)
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION (HI VIZ)
CROFTON II IN-GROUND BASEMENT HI VIZ



RIGHT SIDE ELEVATION (HI-VIZ)
IN-GROUND BASEMENT- WATERTABLE



REAR ELEVATION (HI-VIZ)
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION (HI VIZ)
CROFTON II WALK-OUT BASEMENT HI VIZ



LEFT SIDE ELEVATION (HI-VIZ)
IN-GROUND BASEMENT-WATERTABLE



LEFT SIDE ELEVATION (HI-VIZ)
WALK-OUT BASEMENT-WATERTABLE



RIGHT SIDE ELEVATION (HI-VIZ)
WALK-OUT BASEMENT- WATERTABLE

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HOBION
America's Builder

DRAWN BY:
WADE
DATE: 02.10.26
PROJECT NO. ---
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME: TDG PARK VIEW / EPS MEDFORD NJ
DRAWING TITLE: CROFTON II-BUILDING STRIP HI-VIZ BSMT CONDITIONS

SHEET No.
3

2/26/2026





REAR ELEVATION
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION
CROFTON II IN-GROUND BASEMENT

REAR ELEVATION
CROFTON II IN-GROUND BASEMENT



RIGHT SIDE ELEVATION
IN-GROUND BASEMENT



REAR ELEVATION
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION
CROFTON II WALK-OUT BASEMENT


REAR ELEVATION
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION
CROFTON II WALK-OUT BASEMENT

REAR ELEVATION
CROFTON II WALK-OUT BASEMENT



LEFT SIDE ELEVATION
IN-GROUND BASEMENT



LEFT SIDE ELEVATION
WALK-OUT BASEMENT



RIGHT SIDE ELEVATION
WALK-OUT BASEMENT

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HORION
America's Builder

DRAWN BY:
WADE
DATE: 02.10.26
PROJECT NO. ---
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME: TDG PARK VIEV /EPS MEDFORD NJ
DRAWING TITLE: CROFTON II-BUILDING STRIP W/ BSMT ELEVATIONS

SHEET No.
3D



REAR ELEVATION
CROFTON II SLAB ON GRADE

REAR ELEVATION
CROFTON II SLAB ON GRADE

REAR ELEVATION
CROFTON II SLAB ON GRADE

REAR ELEVATION
CROFTON II SLAB ON GRADE

REAR ELEVATION
CROFTON II SLAB ON GRADE



LEFT SIDE ELEVATION
SLAB ON GRADE



RIGHT SIDE ELEVATION
SLAB ON GRADE

2/26/2026

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638


D·R·HORION
America's Builder

DRAWN BY:
WADE
DATE:
02.10.26
PROJECT NO.

11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
TDG PARK VIEW / EPS MEDFORD NJ
DRAWING TITLE
**CROFTON II-BUILDING STRIP
SLAB ON GR. ELEVATIONS**


SHEET No.
3
11



FIRST FLOOR



SECOND FLOOR




FINISHED BASEMENT

D.R. Horton is equal housing opportunity builder. With basement foundations, water heaters and HVAC systems will be relocated from the first or second floors, as specified per plan. All pricing, included features, terms, availability and amenities, are subject to change at any time without notice or obligation. Elevations and exterior materials may vary. Square footages, measurements and dimensions are approximate and will vary based on foundation type and options selected. Pictures, artist renderings, photographs, colors, features, and sizes are for illustration purposes only and will vary from the homes as built. Options and upgrades are available at an additional cost and are subject to availability and construction cut-off dates DT03-24/40-2343-090520

DRAWN BY:	WADE
DATE:	02-26-26
PROJECT NO.:	DT41
11 X 17 SCALE	1/8" = 1'-0"
24 X 36 SCALE	1/4" = 1'-0"


HOUSE NAME:	MEDFORD - CROFTON-01
DRAWING TITLE:	FLOOR PLANS

SHEET No.	C70-1
-----------	-------





4'-0" CROFTON T3B3 HI-VIZ (RIGHT-HAND) 28'-0" CROFTON U3B3 HI-VIZ (RIGHT-HAND) 28'-0" CROFTON S3B3 HI-VIZ (RIGHT-HAND) 140'-0" CROFTON U3B3 HI-VIZ (RIGHT-HAND) 28'-0" CROFTON T3B3 HI-VIZ (LEFT-HAND) 4'-0"



WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D.R. HORTON
America's Builder

DRAWN BY:
WADE
DATE:
02.10.26
PROJECT NO.
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
TDG PARK VIEW/EPS MEDFORD NJ
DRAWING TITLE
CROFTON - BUILDING STRIP
FRONT EL. & PLAN W/ BSMT

SHEET No.
2A

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·HOBION
America's Builder

DRAWN BY:
WADE
DATE: 02.10.26
PROJECT NO. _____
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME: TDG PARK VIEW / EPS MEDFORD NJ
DRAWING TITLE: CROFTON W/ BSMT
HI-VIZ SIDE & REAR ELE.

SHEET No.
2B



REAR ELEVATION (HI VIZ)
CROFTON- IN GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON- IN GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON- IN GROUND BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON- IN GROUND BASEMENT

REAR ELEVATION (HI VIZ)
CROFTON- IN GROUND BASEMENT



LEFT SIDE ELEVATION - IN GROUND BASEMENT
CROFTON HI VIZ




REAR ELEVATION (HI-VIZ)
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION (HI-VIZ)
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION (HI VIZ)
CROFTON-WALK-OUT BASEMENT



LEFT SIDE ELEVATION - WALK-OUT BASEMENT
CROFTON HI VIZ



RIGHT SIDE ELEVATION- IN GROUND BASEMENT
CROFTON HI VIZ



RIGHT SIDE ELEVATION - WALK-OUT BASEMENT
CROFTON HI VIZ



RIGHT SIDE ELEVATION (SLAB ON GRADE)
CROFTON HI VIZ



LEFT SIDE ELEVATION (SLAB ON GRADE)
CROFTON HI VIZ



CROFTON T3B3 (HI-VIZ) CROFTON U3B3 (HI-VIZ) CROFTON S3B3 (HI-VIZ) CROFTON U3B3 (HI-VIZ) CROFTON T3B3 (HI-VIZ)
RIGHT HAND - SLAB ON GRADE RIGHT HAND - SLAB ON GRADE RIGHT HAND - SLAB ON GRADE RIGHT HAND - SLAB ON GRADE LEFT HAND - SLAB ON GRADE



REAR ELEVATION (HI-VIZ) REAR ELEVATION (HI-VIZ) REAR ELEVATION (HI-VIZ) REAR ELEVATION (HI-VIZ) REAR ELEVATION (HI VIZ)
CROFTON - SLAB ON GRADE CROFTON - SLAB ON GRADE CROFTON - SLAB ON GRADE CROFTON - SLAB ON GRADE CROFTON - SLAB ON GRADE

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·H·O·R·I·O·N
America's Builder

DRAWN BY:
WADE
DATE: 02.10.26
PROJECT NO. _____
11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
TDG PARK VIEW / EPS MEDFORD NJ
DRAWING TITLE
CROFTON W/ SLAB ON GR.
HI-VIZ SIDE & REAR ELE.

SHEET No.
20



RIGHT SIDE ELEVATION
IN-GROUND CROFTON




REAR ELEVATION
CROFTON- IN GROUND BASEMENT

REAR ELEVATION
CROFTON- IN GROUND BASEMENT

REAR ELEVATION
CROFTON- IN GROUND BASEMENT

REAR ELEVATION
CROFTON- IN GROUND BASEMENT

REAR ELEVATION
CROFTON- IN GROUND BASEMENT



LEFT SIDE ELEVATION
WALK-OUT CROFTON



REAR ELEVATION
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION
CROFTON-WALK-OUT BASEMENT

REAR ELEVATION
CROFTON-WALK-OUT BASEMENT



RIGHT SIDE ELEVATION
CROFTON



LEFT SIDE ELEVATION- IN GROUND BASEMENT
CROFTON HI

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·H·O·R·I·O·N
America's Builder

DRAWN BY:
WADE

DATE: 02.10.26

PROJECT NO. _____

11 X 17 SCALE

1/8" = 1'-0"

24 X 36 SCALE

1/4" = 1'-0"

HOUSE NAME:
TDG PARK VIEW /EPS MEDFORD NJ

DRAWING TITLE
CROFTON W/ BSMT
SIDE & REAR ELE.

SHEET No.

20



RIGHT SIDE ELEVATION
CROFTON



4'-0" REAR ELEVATION REAR ELEVATION REAR ELEVATION REAR ELEVATION REAR ELEVATION 4'-0"
CROFTON- SLAB ON GRADE CROFTON- SLAB ON GRADE CROFTON- SLAB ON GRADE CROFTON- SLAB ON GRADE CROFTON- SLAB ON GRADE



LEFT SIDE ELEVATION
CROFTON

2/26/2026

WADE
ARCHITECTURE
HAGERSTOWN, MD 240-452-4638

D·R·H·O·R·I·O·N
America's Builder

DRAWN BY:
WADE
DATE:
02.10.26
PROJECT NO.

11 X 17 SCALE
1/8" = 1'-0"
24 X 36 SCALE
1/4" = 1'-0"

HOUSE NAME:
TDG PARK VIEV /EPS MEDFORD NJ
DRAWING TITLE
CROFTON W/ SLAB ON GR.
SIDE & REAR ELE.

SHEET No.
2E



FRONT 1
Hi-Viz




FRONT 2
Hi-Viz




REAR 1
Hi-Viz



REAR 2
Hi-Viz




UNIT 'OLIVIA'
3 BR INT. UNIT
1,015 S.F.



UNIT 'OAKLEY'
3 BR INT. UNIT
(ADAPTABLE)
954 S.F.

CLIENT:
D.R. HORTON
2040-A BRIGGS ROAD
MT. LAUREL, NJ 08054


PROJECT NAME:
OAKLEY-OLIVIA MODEL
The Landings at Kirby Mills, Medford, New Jersey




HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737

3212 Brigantine Boulevard
BRIGANTINE, NJ 08203
609.953.5373
FAX: 609.953.5737

REVISIONS:		SHEET TITLE: PLANS / ELEVATIONS	
		SCALE: AS NOTED	SHEET NO. SK-1
		PROJ. NO.: DRH-26013	DATE: February 2, 2026



1 10-UNIT BUILDING FIRST FLOOR PLAN
 SK-2 SCALE: 3/16" = 1'-0"



CLIENT:
 D.R. HORTON
 2040-A BRIGGS ROAD
 MT. LAUREL, NJ 08054

PROJECT NAME:
OAKLEY-OLIVIA MODEL
 The Landings at Kirby Mills, Medford, New Jersey



HOLLIDAY ARCHITECTS, Inc.
 JACKSON COMMONS SUITE A4
 30 JACKSON ROAD
 MEDFORD, NJ 08055
 609.953.5373
 FAX: 609.953.5737

3212 Brigantine Boulevard
 BRIGANTINE, NJ 08203
 609.953.5373
 FAX: 609.953.5737

REVISIONS:		SHEET TITLE:	
		10-UNIT BLD'G.	
		SCALE: AS NOTED	SHEET NO.
		PROJ. NO.: DRH-26013	SK-2
		DATE: February 2, 2026	




1
FRONT ELEVATION
SK-3 SCALE: 3/16" = 1'-0" HI-VIZ

FRONT 2
Reversed

FRONT 1
Reversed

FRONT 2

FRONT 1
Reversed



2
LEFT ELEVATION
SK-3 SCALE: 3/16" = 1'-0" HI-VIZ



3
REAR ELEVATION
SK-3 SCALE: 3/16" = 1'-0" HI-VIZ

REAR 1
Reversed

REAR 2


REAR 1
Reversed

REAR 2
Reversed

REAR 1




3
RIGHT ELEVATION
SK-3 SCALE: 3/16" = 1'-0" HI-VIZ



CLIENT:
D.R. HORTON
2040-A BRIGGS ROAD
MT. LAUREL, NJ 08054

PROJECT NAME:
OAKLEY-OLIVIA MODEL
The Landings at Kirby Mills, Medford, New Jersey



HOLLIDAY ARCHITECTS, Inc.
JACKSON COMMONS SUITE A4
30 JACKSON ROAD
MEDFORD, NJ 08055
609.953.5373
FAX: 609.953.5737

3212 Brigantine Boulevard
BRIGANTINE, NJ 08203
609.953.5373
FAX: 609.953.5737

REVISIONS:		SHEET TITLE:	
		10-UNIT BLD'G.	
		SCALE: AS NOTED	SHEET NO.
		PROJ. NO.: DRH-26013	SK-3
		DATE: February 2, 2026	